App F IX 4

*Previous References*
1943-44 Municipal
M. 79-40 (8+9)

File No 76-43
Serial Nos 8, 9, 10, 11

*Later References*

# GENERAL AND REVENUE SECRETARIAT

*Serial Nos* 4

**Part B for** April 1944

**SUBJECT**

Modified estimate for Gubbi Drainage — first stage for Rs 13,720/—

The D P H in Mysore
Comptroller to the Govt of Mysore
Chief Engineer in Mysore
Deputy Commissioner Tumkur Dist

G O No 10763-6 M 76-43-11 dated 21.4.44 sanctioning the above estimate with some observations

12/7

8

From the Director of P H
No e 197-17/42-43 dy 25-11-43
Requests sanction to the modified estimate for Rs 13,720/- for the first stage of the Gubbi Town drainage scheme.

(mel-79-40-9) x flg T

1) An estimate for Rs 41,160/- was sanctioned vide Govt order dy 24-7-43 for the drainage scheme in the Gubbi Town built, the work being executed in three stages and financed by the Govt and the local mel el in equal proportions

2) As regards the modification of the estimate relating to the 1st stage of the Drainage scheme, there is no extra cost involved in it and hence it may be sanctioned after scrutiny by the chief engineer

A

3) A is submitted for orders

Issue 5/12/43

4) The original estimate for Rs ~~this~~ work as necessary for refree comparison so that the modified estimate may be scrutinised well

4) Issue of Govt letter dated

7/12/43

Issue No L 6235 dy 18 12 43

TYPING SECTION - 7 DEC 1943 GEN & P V SECTT

TYPING SECTION - 9 DEC 1943 GEN & P V SECTT

mel Govt A
JM 2/12

N/

From the D P H

No e 197-24/42 dy 3-2-44

To the original estimate of the work

The D·P H reports sanction to the modified estimate for Rs 13, 720/- for the 1st stage of the comprehensive drainage scheme at Gubbi Town which was sanctioned in GO dy 24-7-43, the cost of the comprehensive drainage scheme being Rs 41, 160/-

The same may be approved after securing by the chief Engineer, P W D

Both The original and the modified estimates of the work inspection memo hereto put up subject with reference to para 4 (b) (i) of 17/- A- will be done. If approved

Lawrence
18/2/44

El O 2642 dated 18-2-1944 Cw 18-2-44

Forwarded submitting with Compliments to the Chief Engineer of Mysore P W D for favour of securing of the estimate & early return

By order
Lawrence
18/2/44

ES 512 24/2/44

Esc (a) C 22/2/44

15/2/44

OFFICE OF THE CHIEF ENGINEER OF MYSORE 1944 403 A 40334 Rec'd 23 FEB

Public Works Secretariat | File No 4952/1 of 193

Serial No

No 458

8 nnn

Returned, with compliments to the Secretary to Government, Law Department

2 The modified estimate is scrutinised to Rs 13,720/-

3 The sanctioned estimate contained a lump sum provision of Rs 525/- for constructing 7 Road Crossings This item has been shown as savings in the modified estimate and the connected works are included under Miscellaneous works Omission of an item in an estimate is no saving in that estimate The rates proposed have slightly been corrected The original and the modified estimate amounts remain the same

4 It is necessary to call for separate rates in the case of old slabs for further works

5 The modified estimate amounting to Rs 13,720/- may be approved

29/3/64
Chief Engineer of Mysore,
Camp - Krishnarajsagar

A K /28th

3-4-64

Dft go is subto fin appl

5/4

The modified estimate for Rs 13,720/- may be sanctioned

6-4-64

16-4-64

Note —Contn sheet

WD 01201—GPB—5 000—24 1 35

17

No L 107 63-6 of 21-4-44

Same claims the proposal.

b [illegible]
1/6/44

SUBJECT

mc 76-43-8

No C 197-17/42-43
Enc forwards a copy

OFFICE OF THE
DIRECTOR OF PUBLIC HEALTH
IN MYSORE

*Bangalore, dated* 21th Nov. *1943*

GEN & REV SECRETARIAT 3298 29 NOV 1943 L S G BRANCH

To

The Secretary to Government,
Law Department, Bangalore

SECY LAW DEPT GOVT OF MYSORE

Re Modified estimate for flood drainage 1st stage for Rs 15,720

Adverting to Government order No 3411-21/ L.7-10-9 dated 27th July 1941 sanctioning an estimate for Rs 11,160 for the drainage scheme in the Idgah Maidan, City of Bangalore, carried out in three years, I have the honour to enclose herewith a modified estimate for Rs 15,720/- for the 1st stage, received from the Sanitary Engineer. The Executive Engineer's D.O. letter dated 19th October 1943 containing the reasons for the modifications and the provisions in original estimate are enclosed herewith for the information of Government

The main modifications are as follows -

1) Replacement of semi-pucca top drains by sylo-pattern drains
2) Construction of certain slabs of drains with old stones
   Instead of new stones
3) Replacement of check slabs by slab stones in mortar as per
   (1) section
4) Certain necessary works involving an excess of Rs 630/-

I request you to be so good as to obtain an early sanction of Government to the modified estimate

I have the honour to be,
Sir,
Your most obedient servant,

O Gachemmy
Director of Public Health

(T.T.C

6

-2-

[illegible] 3,976 [illegible] 1st [illegible] [illegible]

-2-

Re-modified estimate for [illegible] - 1st stage

I have the honour to submit herewith a revised estimate for Rs.15,730/- for the first stage of [illegible] for favour of sanction. The details for alterations are as follows :-

1 The semi-pucca top trains have been replaced by cyl-pattern trains since plenty of old slabs are available. The cyl pattern trains have also proved [illegible] to savings due to utilisation of old slabs

2 The following sizes of trains, viz :-
7' (1) section
5" (3) section
6" (3) section
5' (3) section
4' (3) section
3' (1) section
which were all to be constructed with new stones, have now to be constructed with old stones with the same sizes of stones leading to savings

3 As regards 7' (1) section, on account of the old capacity of old drain to carry storm water, two cyl slabs have been replaced by size stones in mortar. These size stones were under any circumstances necessary and since size stones have been adopted, the cyl slabs have been saved

4 Under Item I Miscellaneous for Rs, removal of paint stones &/ kasal bed in front of houses, earthwork for abutment, and tunnels, construction of house connection trains are some of the items contains in all Rs.605/- as an excess over sanctioned deviations

A comparative statement showing the deviations is also enclosed. I request that the modified estimate for Rs.15,730/- may kindly be sanctioned.

J R

To L6235 ncl 76-43-9

Medical Officer

Sir,

With reference to your letter No

C 197-17/4V-47 of 25 11 1943

re modified estimate for the Salta

drainage scheme I am directed to request you to

~~favour~~ forward the original estimate

sanctioned for the I stage for

refee & return

I have the

honour

to be

Sir

Your obedt Servt

16/12

ml 76-43-10

C F No 46] **GOVERNMENT OF MYSORE**

No C 197- 24/42-43 **OFFICE OF** the Director of Public Health
Encls one estimate in Mysore, Bangalore

**Date** 3-2-1944

**To**

The Secretary to Government,
Public Works Department, Bangalore.

**Sir**

GEN & R SECTT 4952 5 FEB 1944 L S G BRANCH

Rcd 7/2

Hubbi Drainage Scheme - 1St Stage

With reference to your letter No L 6235/III 76-43-9 dated 18th December 1943 requesting for the original estimate for Rs 13720/- for the Hubbi Drainage Scheme 1st stage, I have the honour to send the same herewith enclosed for the information of Government

I have the honour to be,

Sir,

Your most obedient servant

Director of Public Health

bnn

G. R. S. App. I

SUBJECT

9

Diary No of letter replied to

General and Revenue Secretariat

( )

the 194

Date of issue 21/4/1944

Signed by

Section Rul

File No 76-43

Serial No 11

*Proceedings of the Government of His Highness the Maharaja of Mysore*

Read— 1. G.O.No R 541-44/Rul 79-40-9 dt 24-7-'41 sanctioning an estimate for ~~Rs 4,60~~ Rs 41,160/- for the comprehensive drainage scheme in the Gubbi Town Ward.

2) Correspondence ending with ~~Order thereon No~~ letter No. C 197-44/42 dt 3-2-44 from the D.P.H in Mysore reporting, in the circumstances stated, sanction to the modified estimate for Rs 13,720/- for the first stage of the Drainage Scheme in the Gubbi Town Ward,

May this be—

(i) printed?

(ii) treated as a Standing Order?

(iii) published in the Gazette English Part?

(iv) translated?

(v) placed at the disposal of the Press?

(vi) published in the Gazette Kannada Part?

(3) No note No 458 of 3-4-44. 10/1
from the Chief Engineer of Mysore,
P. to D on the subject-

10763-6
under No 2 of 21-4-44 with
the modified estimate for Rs 13,720/-
is sanctioned, with the observation that
~~access~~ separate rates in the case of
old slabs for further works in this connection
should be called for and the work got
executed.

Ans 4
8-

for Secy to Govt.

List of Enclosures

To,

The D P H in Mysore WDR
The Comptroller ✓
The Chief Engineer ✓
The D-C Tumkur ✓

Copied by

Examined by

WD 04162—GPB—60 000—23 10 41